	Electric Product Detailed Technical Assumptions															Program Forecast Inputs Stipulated Forecast Inputs					Program Forecast Outputs												
Measure Description		High Efficiency Product Assumptions			Baseline Product Assumptions				Economic Assumptions				Stipulated Output							Economic Assumptions Technical Assumption				2020				2020					
Electric Measure Group	Electric Measure Description	Efficient Product Description / Rating	Efficient Product Consumption (watts)	Efficient Hours of Operation (hrs/yr)	Baseline Product Description / Rating	Baseline Product Consumption (watts)	Baseline Hours of Operation (hrs/yr)	Measure Lifetime (years)	Rebate Amoun (\$)	Average Baseline Product Cost (\$)	Incremental Cos of Efficient Product (\$)	Assumed Energ Cost (\$/kWh)	Rebate as a % of Incrementa Cost (%)	Incremt'l Cost Payback Period w/o Rebate (yrs)	Incremt'l Cost Payback Period w/ Rebate (yrs)	Customer kWI	Rebated Cost Cust kWh Saved (\$/kWh		Customer kW Savings (kW)	Generator Peak kW Savings (kW)	Non-Energy O&M Savings (\$)	Energy O&M Savings (\$)	Coincidence Factor (%)	2020 Participants (-)	2020 Units (-)	NTG (%)	stallation R Rate (%)	Realization Rate (%)	2020 NET Gen kW (kW)	2020 NET Gen kWh (kWh)	2020 Rebate Budget (\$) \$1,585,986	2020 Incremental Costs (\$)	Measure Load Shape
Multifamily Audit	Audit Services	Multifamily Building Audit			None				\$196.15	\$0	\$196.15	\$0.03	100%	#DIV/0!	#DIV/0!	0	#DIV/0!	#DIV/0!	0.00000	0.00	\$0.00	\$0.00	0%	0	0	100%	100%	100%	0	11,569,634	\$1,585,986	\$2,355,167	CO-BUS-FLAT
Multifamily Audit	Audit Services	Multifamily Building Audit			None				\$201.50	\$0	\$201.50	\$0.03	100%	#DIV/0!	#DIV/0!	0	#DIV/0!	#DIV/0!	0.00000	0.00	\$0.00	\$0.00	0%	15	1,650	100%	100%	100%	0	0	\$332,474	\$332,474	CO-BUS-FLAT
Direct Install - LED	Replace incandescent lamps with LEDs	LED lamp	9.8	986	Average EISA Standard Halogen Bulb	45	986	5.00	\$5.39	\$0	\$5.39	\$0.12	100%	1.27	-	35	\$0.154	\$0.031	0.03557	0.00	\$0.00	\$0.00	13%	1,205	130,168	100%	100%	100%	643	4,876,936	\$701,269	\$701,269	CO-RES-MFLIT
Multifamily Showerhead	Provide new 1.5 gpm showerhead to replace existing 2.5 gpm showerhead in electric DHW heater	1.5 GPM Showerhead	94	8,760	2.5 GPM Showerhead	157	8,760	10.00	\$14.93	\$0	\$14.93	\$0.12	100%	0.16	-	550	\$0.027	\$0.003	0.06	0.04	\$29.53	\$0.00	64%	1	70	100%	100%	100%	3	41,336	\$1,051	\$1,051	CO-RES-SFMFLOW
Multifamily Kitchen Aerator	Provide Energy Efficient Kitchen Aerator - 1.5 GPM to replace existing 2.2 gpm aerator in home with electric DHW heater	1.5 GPM Kitchen Faucet Aerator	17	8,760	2.2 GPM Kitchen Faucet Aerator	25	8,760	10.00	\$5.20	\$0	\$5.20	\$0.12	100%	0.44		70	\$0.074	\$0.007	0.01	0.01	\$3.39	\$0.00	124%	0	26	100%	100%	100%	0	1,980	\$137	\$137	CO-RES-SFMFLOW
Multifamily Bathroom 1.0GPM Aerator	Provide Energy Efficient Bath Faucet Aerator - 1.0 GPM to replace existing 2.2 gpm aerator in home with electric DHW heater	1.0 GPM Bathroom Faucet Aerator	6	8,760	2.2 GPM Bathroom Faucet Aerator	14	8,760	10.00	\$4.17	\$0	\$4.17	\$0.12	100%	0.37		65	\$0.064	\$0.006	0.01	0.01	\$3.50	\$0.00	124%	0	33	100%	100%	100%	0	2,299	\$138	\$138	CO-RES-SFMFLOW
Multifamily Bathroom 0.5 GPM Aerator	Provide Energy Efficient Bath Faucet Aerator - 0.5 GPM to replace existing 2.2 gpm aerator in home with electric DHW heater	0.5 GPM Bathroom Faucet Aerator	3	8,760	2.2 GPM Bathroom Faucet Aerator	14	8,760	10.00	\$4.22	\$0	\$4.22	\$0.12	100%	0.26	-	92	\$0.046	\$0.005	0.01	0.01	\$4.96	\$0.00	124%	0	0	100%	100%	100%	0	0	\$0	\$0	CO-RES-SFMFLOW
Direct Install - LED Exit Sign	Exit sign retrofit	LED/LEC Exit Sign	2	8,760	Incandescent Exit Sign	37	8,760	20.00	\$24.78	\$0	\$24.78	\$0.06	100%	1.52	-	304	\$0.082	\$0.004	0.03	0.04	\$0.00	-\$0.80	100%	0	0	100%	100%	100%	0	0	\$0	\$0	CO-BUS-FLAT
Energy Star Smart Thermostat	Install Energy Star certified smart thermostat - AC & GAS	Energy Star Certified Thermostat	5,943	765	Manual or programmable thermostat	6,531	765	10.00	\$12.60	\$0	\$12.60	\$0.28	100%	0.10	-	450	\$0.028	\$0.003	0.59	0.00	\$0.00	\$0.00	0%	0	20	100%	100%	100%	0	9,499	\$252	\$252	CO-BUS-COOL_OUT
Energy Star Smart Thermostat	Install Energy Star certified smart thermostat - AC ONLY	Energy Star Certified Thermostat	5,943	765	Manual or programmable thermostat	6,531	765	10.00	\$14.26	\$0	\$14.26	\$0.28	100%	0.11	-	450	\$0.032	\$0.003	0.59	0.00	\$0.00	\$0.00	0%	0	6	100%	100%	100%	0	2,850	\$86	\$86	CO-BUS-COOL_OUT
Energy Star Smart Thermostat	Install Energy Star certified smart thermostat - AC & ELEC HEAT	Energy Star Certified Thermostat	5,943	1,283	Manual or programmable thermostat	6,531	1,283	10.00	\$22.66	\$0	\$22.66	\$0.18	100%	0.16	-	754	\$0.030	\$0.003	0.59	0.00	\$0.00	\$0.00	0%	0	6	100%	100%	100%	0	4,779	\$136	\$136	CO-BUS-COOL_OUT
Energy Star Smart Thermostat	Install Energy Star certified smart thermostat - Combo Customer	Average Multifamily Unit with EnergyStar Smart Thermostat	913	573	Average Multiple Family House with Standard Thermostat	1,015	573	10.00	\$48.25	\$0	\$48.25	\$0.12	100%	6.87	-	58	\$0.830	\$0.083	0.10	0.08	\$0.00	\$0.00	76%	5	500	100%	100%	100%	42	31,055	\$24,123	\$24,123	CO-Res_Cooling_DX
Prescriptive or Custom Project	Average Project	More Efficient than Code Building	27,423	6,700	Code-Compliant Building	34,279	6,700	20.00	\$3,870	\$0	\$9,526	\$0.06	41%	3.39	9 2.01	45,934	\$0.084	\$0.004	6.86	5.09	-\$76.86	\$0.00	69%	1	136	100%	100%	100%	693	6,598,899	\$526,320	\$1,295,500	CO-BUS-FLAT