

2017 Annual Inspection Report

for Compliance with the Coal
Combustion Residuals Rule
(40 CFR Part 257)

Valmont Station

*1800 North 63rd Street
Boulder, Colorado 80301*

January 18, 2018




Table of Contents

Certification	ii
1 Introduction	1
2 Site Inspection	1
3 Review of Available Information	2
4 Visual Inspection.....	2
5 Changes in Geometry.....	3
6 Approximate CCR Volume.....	4
7 Appearance of Structural Weakness	4
8 Changes Affecting Stability or Operation.....	4

Appendices

Appendix A: Landfill Site Map

Certification

Valmont Station CCR Unit 2017 Annual Inspection for Compliance with the Federal Coal Combustion Residuals Rule

I hereby certify that the Coal Combustion Residuals (CCR) unit (i.e. the landfill) at Valmont Station meets the inspection and operation standards specified in 40 CFR Part 257.84(b) of the Federal CCR Rule. The Valmont Station is owned by the Public Service Company of Colorado (PSCo), an Xcel Energy Company.

I am duly licensed Professional Engineer under the laws of the State of Colorado.



Brian Brown, PE

Colorado PE License 0041644

License renewal date October 31, 2019

1 Introduction

On April 17, 2015 the U.S. Environmental Protection Agency (EPA) published regulations under Subtitle D of the Resources Conservation and Control Act (RCRA) meant to control the safe disposal of coal combustion residuals (CCR) generated by coal fired electric utilities. The rule defines a set of requirements for the disposal and handling of CCR within CCR units (defined as either landfills or surface impoundments). As specified in 40 CFR 257.84(b), *“Existing and new CCR landfills and any lateral expansion of a CCR landfill must be inspected on a periodic basis by a qualified professional engineer to ensure that the design, construction, operation, and maintenance of the CCR unit is consistent with recognized and generally accepted good engineering standards.”* Valmont Station has one (1) CCR landfill subject to the inspection requirements.

This is the third annual inspection report for the existing Valmont CCR landfill. This report must be completed and placed into the facility operating record no later than January 18, 2018.

The requirements of the annual inspection include:

- A review of available information regarding the status and condition of the CCR unit - §257.84 (B)(1)(i),
- A visual inspection of the CCR unit to identify signs of distress or malfunction - §257.84 (B)(1)(ii),
- An inspection report that includes the following:
 - Changes in geometry since the last inspection - §257.84 (B)(2)(i)
 - Approximate volume of CCR in unit at time of inspection - §257.84 (B)(2)(ii)
 - Appearance of actual or potential structural weakness of the CCR unit - §257.84 (B)(2)(iii)
 - Any other changes which may have affected the stability or operation of the CCR unit since the last inspection - §257.84 (B)(2)(iv)

2 Site Inspection

In accordance with §257.84(b)(ii), a site inspection of the Valmont CCR Landfill was conducted by an independent Professional Engineer on November 17, 2017. The inspection was conducted by Brian Brown, Doug Decesare, John Ballegeer, all Colorado Professional Engineers of HDR Engineering Inc. (HDR) and John Pierce (Colorado PE), Jennifer McCarter, and Marie Vagher, of PSCo with past and current involvement at the landfill. This site inspection was performed in advance of the CCR submittal deadline to ensure that the inspection was completed prior to snow covering the ground.

The weather during the site visit was sunny with temperatures around 60 degrees Fahrenheit. The site was free of snow cover.

3 Review of Available Information

Numerous documents pertaining to the site operation and structural integrity were reviewed including:

1. Engineering Design and Operation Plan (EDOP), Revision January, 2009 by PSCo. PSCo reported no change in document and still operating under this document. Document not reviewed again since the document is unchanged.
2. Available Weekly CCR Landfill Inspection Forms (per Section 257.84(a)).
3. Topographic Map with Soil Boring Locations: Locations of Exploratory Borings and available cell fill quantity, Check date October 31, 2017, developed by Merrick & Company.

Review of the above documents did not contain any indications of continuing operational, safety, or structural concerns regarding the CCR landfill.

4 Visual Inspection

The site inspection included walking or driving the entire perimeter of the landfill, the interior access road, and select intermediate elevations along the exterior fill embankment.

The site inspection included an evaluation of the following landfill features:

1. landfill side slope toe of slope;
2. Landfill side slope benches;
3. Riprapped stormwater drainage conveyance channels on southwest side (Areas Q-1 and A-3) of landfill and east end (Area B-1) of landfill; and
4. Active CCR fill areas (CCR disposal, spreading, and compaction).

The following are the findings of the site inspection:

The landfill side slopes showed no signs of operational or functional concerns. Areas of erosion are noted below:

- The landfill side slopes along the southwest and west side of Area Q-1 have minimal vegetation cover. Despite the presence of regular benches to slow the stormwater flow, these areas show signs of rill and some gully erosion. These areas require continued monitoring and may require additional topsoil cover and revegetation to minimize future rill erosion.
- The western side slopes of the landfill also had numerous prairie dog burrows. These burrows should continue to be monitored as they can impact local slope stability and

become conduits for stormwater flow. PSCo reported that it has implemented measures to minimize prairie dog burrow impacts in the soil cover, with limited success. PSCo has indicated that ongoing maintenance will be implemented to will continue to address this issue.

- The southern slopes of Area Q-1 had some apparently inactive rill erosion near the top of the slope that should be monitored.
- The inactive southeastern and eastern side slopes have a continuous grade that generally ranges from approximately 2 horizontal to 1 vertical (2H:1V) to 3H:1V with some steeper sections, no benches, and a dense stand of vegetation.
 - There is a riprap run down on the east slope (Area B-1) with no visible erosion or stability concerns.
 - The south slope is an area where sloughing and localized instability is visible about one quarter down from the top plateau (against a degraded line of straw bales). This area is heavily vegetated but should be monitored for future sloughing or movement. The consensus of the HDR engineers was to continue monitoring the area. No additional movement, including surface tension cracks, or sloughing was observed since the prior annual inspection.
- The interior access road leading to the active landfill fill area has steep soil embankments. The level of erosion observed during the inspection indicates that the access road embankments do not receive enough surface water run-on flow to create excessive rill or gully erosion. The roadway embankments should be monitored for localized or general sloughing, though none was observed.
- The north facing landfill embankment of areas D1, E1 and B1 are graded to a uniform slope. This slope does not have benches but does have a dense cover of vegetation. No erosion or sloughing was noted.
- The active fill area (Area D-1) was observed to have minimal areas of exposed ash. The recently soil covered CCR landfill work areas on the western side of Area D-1 appeared to have adequate soil cover. Side slopes for the cell excavation between the two fill areas were steep but showed no signs of instability or erosion.
- No ash disposal or compaction was observed during the site visit.
- There was no standing water observed in the active ash fill area.

5 Changes in Geometry

The Federal CCR Rules require that site geometry changes be identified since the last inspection. The site footprint remains the same since the prior site visit. The eastern face of the active area within Area D-1 has moved west due to the continued CCR disposal.

No structural or safety concerns were observed due the continued site geometric filling. Fill is expected to continue in a similar manner for 2018 as well as place material on top of cell.

6 Approximate CCR Volume

The CCR within the disposal area as of November 2015 was estimated by PSCo based on volume estimates that utilized topographic surveys, disposal records, ash generation volumes, and extrapolation of generation volumes. The total combined volume of CCR deposited within the landfill through October 2016 is estimated to be 1,344,200 cubic yards. The additional CCR deposited from November 1, 2016 through November 30, 2017 is estimated to be 71,510 CY, assuming one cubic yard of CCR material equates to one ton. The total CCR volume in the landfill as of November 30, 2017 is estimated to be 1,415,710 CY. Disposal in 2017 included material from the coal unit operations and cleanout of baghouses and the silo after operations ceased. The landfill will remain active in 2018, receiving dry bottom ash from cleanout of the on-site temporary storage ponds.



7 Appearance of Structural Weakness

Based on the site inspection, no apparent or potential structural weaknesses were observed. Per Section 4 above, continued monitoring and minor repairs should be considered to address rill erosion and prairie dog burrows before these issues become a structural landfill weakness. Much of the site's exterior rill erosion will be addressed as the recent lifts are covered in topsoil, seeded, and vegetation is established. Further erosion impacted areas may require additional mitigation measures.

8 Changes Affecting Stability or Operation

The Federal CCR Rule requires that changes that affect site stability or operation be identified since the last inspection. Since the last annual inspection, there were no observed nor reported operational changes or site conditions that indicate issues of stability or safety.

Appendix A – Landfill Site Map



LEGEND


[Green Box]	A-1
[Light Green Box]	A-2
[Yellow Box]	A-3
[Purple Box]	B-1
[Blue Box]	C-1
[Light Blue Box]	D-1
[Pink Box]	E-1
[Light Pink Box]	Q-1
[Light Purple Box]	Q-2
[HV Symbol]	MONUMENT
[Transmission Line Symbol]	TRANSMISSION LINE
[MW Symbol]	GW MONITOR WELL

MONUMENT CONTROL SCHEDULE

CONTROL POINT NUMBER	MODIFIED NAD83 (1992) NORTHING	MODIFIED NAD83 (1992) EASTING	ELEVATION
240	1253563.43	3083969.33	5287.75
241	1253989.48	3082897.93	5281.08
242	1253532.52	3083523.78	5291.01
243	1253980.56	3084091.23	5283.43
245	1253132.36	3084626.33	5231.38
247	1253974.13	3085140.27	5277.96
251	1253180.17	3085119.97	5230.59
252	1253058.55	3084101.66	5231.14
253	1253835.34	3083158.54	5232.40

AREA TABLE

AREA NAME	AREA (AC)	ESTIMATED STORAGE CAPACITY		CLOSURE DATE
		VOLUME (CY)	LIFE (YR)	
A-1	3.02	0	0.0	7/09
A-2	12.20	0	0.0	7/09
A-3	2.82	0	0.0	7/09
B-1	5.55	0	0.0	12/08
C-1	6.83	85,534	0.7	7/14
D-1	9.67	254,357	2.1	7/13
E-1	4.90	5,200	0.0	7/13
Q-1	10.29	245,768	2.0	12/11
Q-2	2.76	0	0.0	12/11
		590859	4.8	7/14



VALMONT SEGS - COMMON

ASH DISPOSAL FACILITY AREA MAP

PUBLIC SERVICE COMPANY OF COLORADO
AN ILLINOIS ENERGY COMPANY

FIG 0-1

DWN: TC DATE: 07/27/08
CHK: JH DATE:

25-2.73

SHEET 1 REV 0

MF NO 01/19/09 DR JP ISSUE FOR CONSTRUCTION PER JULY, 2008 SURVEY - 1904293
NO DATE DWN CHK REVISION E M C MF

FILENAME: 25-2.73 SH1
R-CODE: 1380029
SCALE: NTS

FILENAME: 25-2.73 SH.1

